

NOTA DE SERVIÇO DE TERRAPLENAGEM
RUA EMILIO RIBEIRO - BOM JARDIM DA SERRA SC

C:\Venicio\Municipios\Bom Jardim\RUA EMILIO RIBEIRO PROJ ASFALTICO\PERFIL RUA EMILIO RIBEIRO per

Est	Dist	Cota	Alt	Inicio		Bordo		Eixo		Bordo		Offset								
				Talude	Cota	Dist	Cota	%	Terr	Proj	Vern	Dist	Cota	Talude	Dist	Cota	Alt			
0				5,650	1246,880	4,000	1246,730	-2,0	1246,810	1246,810	-0,000	4,000	1246,730	-2,0	5,650	1246,881				
0+5,535				5,650	1246,030	4,000	1245,880	-2,0	1245,942	1245,960	-0,018	4,000	1245,880	-2,0	5,650	1246,031				
1				5,650	1243,808	4,000	1243,658	-2,0	1243,818	1243,738	0,080	4,000	1243,658	-2,0	5,650	1243,809				
1+6,591				5,650	1242,796	4,000	1242,646	-2,0	1243,503	1242,726	0,777	4,000	1242,646	-2,0	5,650	1242,797				
2				5,650	1240,736	4,000	1237,514	-2,0	1237,592	1240,666	-0,119	4,000	1240,586	-2,0	5,650	1240,737				
3				5,650	1237,664	4,000	1234,717	-2,0	1234,749	1234,797	-0,048	4,000	1234,717	-2,0	5,650	1237,665				
4				5,650	1234,867	4,000	1232,482	-2,0	1232,523	1232,562	-0,039	4,000	1232,482	-2,0	5,650	1234,868				
5+8,623				5,650	1231,844	4,000	1231,694	-2,0	1231,838	1231,774	0,064	4,000	1231,694	-2,0	5,650	1232,633				
6				5,650	1230,852	4,000	1230,702	-2,0	1230,948	1230,782	0,166	4,000	1230,702	-2,0	5,650	1231,845				
6+7,645				5,650	1230,185	4,000	1228,958	-2,0	1230,153	1230,115	0,038	4,000	1230,035	-2,0	5,650	1230,853				
7				5,650	1229,108	4,000	1227,643	-2,0	1228,990	1227,938	-0,048	4,000	1228,958	-2,0	5,650	1230,186				
7+16,118				5,650	1227,793	4,000	1227,412	-2,0	1227,833	1227,723	-0,110	4,000	1227,643	-2,0	5,650	1229,109				
8				5,650	1227,562	4,000	1227,009	-2,0	1227,586	1227,492	0,094	4,000	1227,412	-2,0	5,650	1227,794				
8+10,017				5,650	1227,159	4,000	1226,874	-2,0	1226,817	1226,874	-0,057	4,000	1226,794	-2,0	5,650	1227,160				
9				5,650	1226,944	4,000	1226,627	-2,0	1226,703	1226,707	-0,004	4,000	1226,627	-2,0	5,650	1226,945				
9+7,966				5,650	1226,777	4,000	1226,376	-2,0	1226,365	1226,456	-0,091	4,000	1226,376	-2,0	5,650	1226,778				
9+19,903				5,650	1226,526	4,000	1226,374	-2,0	1226,364	1226,454	-0,090	4,000	1226,374	-2,0	5,650	1226,527				
10				5,650	1226,524	4,000	1225,954	-2,0	1226,021	1226,034	-0,013	4,000	1225,954	-2,0	5,650	1226,525				
11				5,650	1226,104	4,000	1225,912	-2,0	1225,999	1225,992	0,008	4,000	1225,912	-2,0	5,650	1226,105				
11+14,09				5,650	1226,062	4,000	1225,894	-2,0	1225,947	1225,974	-0,027	4,000	1225,894	-2,0	5,650	1226,045				
12				5,650	1226,044	4,000	1225,845	-2,0	1225,998	1225,925	0,074	4,000	1225,845	-2,0	5,650	1225,996				
12+16,47				5,650	1225,995	4,000	1225,834	-2,0	1225,945	1225,914	0,031	4,000	1225,834	-2,0	5,650	1225,995				
13				5,650	1226,278	4,000	1226,128	-2,0	1226,183	1226,208	-0,025	4,000	1226,128	-2,0	5,650	1226,279				
14				5,650	1226,349	4,000	1226,199	-2,0	1225,670	1226,279	-0,609	4,000	1226,199	-2,0	5,650	1226,350				
14+10,37				5,650	1226,349	4,000	1226,199	-2,0	1225,670	1226,279	-0,609	4,000	1226,199	-2,0	5,650	1226,350				
2				5,650	1226,639	4,000	1226,489	-2,0	1226,582	1226,569	0,013	4,000	1226,489	-2,0	5,650	1226,640				
15				5,650	1226,901	4,000	1226,751	-2,0	1226,843	1226,831	0,012	4,000	1226,751	-2,0	5,650	1226,902				
15+7,684				5,650	1227,406	4,000	1227,256	-2,0	1227,539	1227,336	0,203	4,000	1227,256	-2,0	5,650	1227,407				
16				5,650	1228,571	4,000	1228,421	-2,0	1228,629	1228,501	0,128	4,000	1228,421	-2,0	5,650	1228,572				
17				5,650	1229,911	4,000	1229,761	-2,0	1229,741	1229,841	-0,100	4,000	1229,761	-2,0	5,650	1229,912				
18				5,650	1231,679	4,000	1231,529	-2,0	1231,540	1231,609	-0,069	4,000	1231,529	-2,0	5,650	1231,680				
19				5,660	1232,035	4,000	1231,885	-2,0	1231,966	1231,965	-0,009	4,000	1231,885	-2,0	5,660	1232,036				
19+3,833				5,660	1232,035	4,000	1231,885	-2,0	1231,966	1231,965	-0,009	4,000	1231,885	-2,0	5,660	1232,036				

