

NOTA DE SERVIÇO DE TERRAPLENAGEM RUA AGENOR MACHADO - BOM JARDIM DA SERRA SC

	Offset				Inicio Talude		Bordo				Eixo			Bordo			Inicio Talude		Offset		
	Est	Dist	Cota	Alt	Dist	Cota	Dist	Cota	%	Terr	Proj	Verm	Dist	Cota	%	Dist	Cota	Dist	Cota	Alt	
0					4,20	1243,477	3,000	1243,327	-2,0	1243,487	1243,387	0,100	3,000	1243,327	-2,0	4,20	1243,478				
0+15.143					4,20	1243,516	3,000	1243,366	-2,0	1243,678	1243,426	0,252	3,000	1243,366	-2,0	4,20	1243,517				
1					4,20	1243,529	3,000	1243,379	-2,0	1243,632	1243,439	0,193	3,000	1243,379	-2,0	4,20	1243,530				
1+17.502					4,20	1243,575	3,000	1243,425	-2,0	1243,654	1243,485	0,169	3,000	1243,425	-2,0	4,20	1243,576				
2					4,20	1243,581	3,000	1243,431	-2,0	1243,646	1243,491	0,155	3,000	1243,431	-2,0	4,20	1243,582				
2+12.157					4,20	1243,613	3,000	1243,463	-2,0	1243,565	1243,523	0,042	3,000	1243,463	-2,0	4,20	1243,614				
3					4,20	1243,568	3,000	1243,418	-2,0	1243,495	1243,478	0,017	3,000	1243,418	-2,0	4,20	1243,569				
3+6.944					4,20	1243,394	3,000	1243,244	-2,0	1243,286	1243,304	-0,018	3,000	1243,244	-2,0	4,20	1243,395				
4					4,20	1242,945	3,000	1242,795	-2,0	1243,032	1242,855	0,177	3,000	1242,795	-2,0	4,20	1242,946				
5					4,20	1242,257	3,000	1242,107	-2,0	1242,358	1242,167	0,191	3,000	1242,107	-2,0	4,20	1242,258				
5+13.276					4,20	1241,800	3,000	1241,650	-2,0	1241,734	1241,710	0,024	3,000	1241,650	-2,0	4,20	1241,801				
6					4,20	1241,569	3,000	1241,419	-2,0	1241,580	1241,479	0,101	3,000	1241,419	-2,0	4,20	1241,570				
6+6.143					4,20	1241,358	3,000	1241,208	-2,0	1241,280	1241,268	0,013	3,000	1241,208	-2,0	4,20	1241,359				
7					4,20	1240,913	3,000	1240,763	-2,0	1240,790	1240,823	-0,033	3,000	1240,763	-2,0	4,20	1240,914				
7+20.000					4,20	1240,620	3,000	1240,470	-2,0	1240,529	1240,530	-0,001	3,000	1240,470	-2,0	4,20	1240,621				